

SLIM-LINE BUILT-IN VIEWING AREA CENTERING DIMENSIONS

Clearances to Combustibles: Top and Sides: 4", Bottom: ½" Please note: Single sided models can be ordered with left or right side venting **READ INSTALLATION MANUAL BEFORE INSTALLATION**

Dimension	Dimension Description	FORTY8	SIXTY0	SEVENTY2
"AA"	Viewing Area	49.25" (1,251mm)	59.25" (1,505mm)	73.25" (1,861mm)
"BB"	Non-flue side spacing	2.70" (69mm)	2.70" (69mm)	2.70" (69mm)
"CC"	Flue side spacing	11.30" (287mm)	11.30" (287mm)	11.30" (287mm)
"DD"	Non-combustible requirement, side	4.00" (102mm)	4.00" (102mm)	4.00" (102mm)
"EE"	Distance required to center viewing area	35.93" (913mm)	40.93" (1,040mm)	47.93" (1,217mm)
"FF"	Distance required to center viewing area, including non-combustible requirement	39.93" (1,014mm)	44.93" (1,141mm)	51.93" (1,319mm)
"GG"	Minimum wall space required to center viewing area	71.85" (1,825mm)	81.85" (2,079mm)	95.85" (2,435mm)
"HH"	Minimum wall space required to center viewing area including non-combustible requirement	79.85" (2,028mm)	89.85" (2,282mm)	103.85" (2,638mm)

